# Nikuni KTM Series Pumps

( Micro Bubble Generator for DAF System )

Client : Project :

Model : KTM50S2-000 (SS304 material)

Date: Doc. No.: Revision No.:



#### Japan Headquarters:

843-5, Kuji, Takatsu-Ku, Kawasaki-Shi, Kanagawa, Japan Post-code 213-0032 URL: http://www.nikuni.co.jp

Phone: +81-44-833-6500 (English)

+81-44-833-1121 (Japanese)

Fax: +81-44-833-6482

MAIN OFFFICE :

REV. DATE

COMMENT

DESCRIPTION

DRAWN BY

CHECK BY


APPROVED BY


843-5 KUJI, TAKATU-KU, KAWASAKI, KANAGAWA, JAPAN 2130032




TEL: +81(0)-44-833-6500 FAX: +81(0)44-833-6482						NIKUNI BUBBLE GENERATOR FOR DAF SYSTEM				
			N	IKUNI KTM (DA	F) P	UMP DA	ATA S	HEET		
Compar	ny					Date				
Project						Data shee	t No.			
Service						Rev.				
Item No	)					PID No.				
No.Ope	rating			No.Spare		Total Rec	uired			
Pump M		КТ	M50S2-00	00 (SS304 material)			1			
Pump T				pe (Base plate, Coup	oling	set & Cou	pling g	uard only)		
1	J1			PROCESS AND P				-		
Condit	ions of S	Service.	Each Pu	mp						
Fluid	20125 01 8	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		Treated Water		Design C	apacity	(L/min / gpm)	/	
	Capacity	/ (L/min	/ m3/Hr)			<u> </u>	<u> </u>	MPa / bar)	-0.03 / -0.3	
	ature (°C		/ III3/III)	200 / 12.0		Disch. Pro			/	
	Gravity		)					s. (MPa / bar)	,	
	ty (at P.T					Total Hea		` ′	30 or 40 / 3 or 4	
	•		Nm3/Hr)	16 / 0.96				d (m / bar)	30 01 40 7 3 01 4	
	Ava. (m)	<b>L</b> /111111 / .	14113/111)	10/0.90		NPSH Re		a (m / oai)	+	
	Driver					IVI SII KC	q. (III)			
		should b	ne prepare	d by purchaser						
Phase	ic motor	Silouid	oc prepare	Output (kW / H)	D)	7.51-W/ /	10 HD	Frequency	50 Hz	
					P)	7.5kW / 10 HP Frequency 4 Speed				
Voltage	<del> </del>			Pole		т пресси			1500 min-1	
Type	1 1	1-411	1.1	to IEC Material Course	1	12234				
* Origin		nate will	i be fixed	to IEC Motor frame	size	132IVI .				
		Size	e 50 A			Datina	JIS 10	OIZ		
(Suction						Rating	+			
(Discha		Size				Rating	JIS 10	JK		
	als (Wet			a. c	GI	10204		G 0:	Dance	
Casing		SCS13		Shaft	-	JS304		Cover O-ring	PTFE	
Impelle	r	SUS30		Side plate		ic - Sic , PTFE		Slinger	NBR	
Cover		SCS13	5	Mechanical Seal	S10	c - Sic , P	IFE			
Paintin										
MUNSI	ELL N3									
Remar										
Accesso	•									
	In-take n									
Plea	ise refer t	o attache	ed recomn	nendation of the air-p	paran	neter & gu	ages ra	nges and other a	iccessories.	
			<del></del>							
-										
DEV	DATE	COM	4ENT	DECEDIBITION		DD A WA	DV	CHECK DV	A DDD OVED DA	

#### Dimension





Coupling Dimension for KTM50S(F)1, S2(F2) & S3(F)



Coupling l	Dime	nsion	(unit:	mm)			
kw	A	В	С	D	Е	F	SS
5.5,7.5	45	45	90	38	41.3	10	24
11 15	55	55	120	42	45 3	12	40

Applicable motor frame size for Original base-plate.

kW	IEC Frame
5.5	132S
7.5	132M
11	160M
15	160L


### Demension & net weight

Unit:mm

Model	Kw	HP	S	D	PR	PY	FA	FB	FS	FC	MH	L	MA	MR	SS	VE	VF	VM	VN	VS	VT	VZ	KL	Weight
KTM50S1	5.5	7.0	50A	50A	285	160	130	55	150	230	204	836	210.5	239	24	324	448	352	690	121	20	12	189	90
KTM50S2	7.5	10	50A	50A	285	170	130	55	160	240	204	874	229.5	258	24	324	448	352	690	121	20	12	189	110
KTM50S3	11	15	50A	50A	285	170	130	55	169	240	245	1027.5	302	323	40	368	614	404	878	132	20	15	257.5	125

\*Approx. Packing weight (Motor weight not included)


#### Sectional Drawing



#### Material


No.	NAME OF PARTS	SET	MATERIALS
021	Ball Bearing	1	SUJ
022	Ball Bearing	1	SUJ
025	Bracket	1	FC200
027	Bearing Gland	1	SPC
051	Mechanical Seal	1	SiC - SiC
074	Key	1	S45C
081	Slinger	1	NBR
102	Casing	1	SCS13
103	Cover	1	SCS13
107	Impeller	1	SUS304
108	Shaft	1	SUS304
113, 114	Key, washer & nut	1	SUS304
116	Impeller Key	1	SUS316
123	Cover O-Ring	1	PTFE






#### Air Intake Nozzle (Included in every package)

How to connect the nozzle to Air Flow Meter (Air Intake Nozzle will be attached to every pump)







Applicalbe Model (Standard)	Dia. (E)	Length (L1)	Length (L2)	Length (L)	Dia. (D)
KTM15 (F)(N)(D)	R 3/8 <sup>B</sup>	121	73	157	R 1/4 <sup>B</sup>
KTM20 (F)(N)(D)	R 3/8 <sup>B</sup>	121	88	162	R 1/4 <sup>B</sup>
KTM25 (F)(N)(D)	R 3/8 <sup>B</sup>	121	97	167	R 1/4 <sup>B</sup>
KTM32 (F)(N)(D)	R 3/8 <sup>B</sup>	121	114	172	R 1/4 <sup>B</sup>
KTM40 (F)(N)(D)	R 3/8 <sup>B</sup>	121	120	177	R 1/4 <sup>B</sup>
KTM50 (F)(S)1,2,3	R 3/8 <sup>B</sup>	129	210	268	R 1/4 <sup>B</sup>

Applicable Model (Large-scaled Type)	Dia. (E)	Length (L1)	Length (L2)	Length (L)	Dia. (D)
KTM65S2 / F2	Rc 3/8	183	240	304	Rc 3/8
KTM80S / F	Rc 3/8	193	240	319	Rc 3/8

<sup>\*</sup> In case of KTM80S / F model, connect "E" part with Bushing (3/4 x 3/8)




- 1) Loosen the nuts of the lower pipe joint to allow a nipple to freely move.
- 2) Mark the pipe bending direction on the pipe surface between the upper and lower pipe joints.
- 3) Wind a sealing tape around the lower pipe joint's nipple of the suction nozzle, insert it into the nozzle junction of the pump, and turn the nipple to firmly fix it.
- 4) Turn the pipe to align the mark on the pipe surface so that the bend nose (gas discharge port) of the pipe will be directed to the center of the impeller.
- 5) Tighten the nuts of the lower pipe joint firmly. Make sure that the suction nozzle is not manually rotated.
- 6) Rotate the motor manually (rotate the shaft end of the motor with a screwdriver) to make sure that the pipe nose of the nozzle is not interfering with the impeller.



#### Recommended Accessories (To be prepared by Purchaser)

#### Air Parameter





Compound Guage Minus 0.1 MPa to + 0.25MPa Minus 1.0 Bar to + 2.5 Bar Minus 15psi to + 35 psi

Guages



Pressure Guage 0 MPa to + 1.0MPa 0 Bar to + 10 Bar 0 psi to + 150 psi

#### Operation air flow rate & Air Parameter ranges

50Hz Frequency									
Applicalbe Model (Standard)	Water Flow Rate m <sup>3</sup> /Hr x 4Bar	Operation Air flow rate (N•L/min)	Air Flow Meter Range (N°L/min)						
KTM20 (F)(N)(D)	1.0	1.3	0 to 5						
KTM25 (F)(N)(D)	1.5	2.0	0 to 5						
KTM32 (F)(N)(D)	3.0	4.0	0 to 10						
KTM40 (F)(N)(D)	4.8	6.4	0 to 10						
KTM50S1 / F1	8.0	10.6	0 to 20						
KTM50S2 / F2	12.0	16.0	0 to 20						
KTM50S3 / F3	15.0	20.0	0 to 30						
KTM65S2 / F2	20.0	26.6	0 to 40						
KTM80S / F	42.0	56.0	0 to 80						

COLLE E

60Hz Freque	ency	
Water Flow Rate m <sup>3</sup> /Hr x 4Bar	Operation Air flow rate (N*L/min)	Air Flow Meter Range (N*L/min)
1.3	1.7	0 to 5
2.5	3.3	0 to 5
4.0	5.3	0 to 10
7.0	9.3	0 to 20
11.5	15.0	0 to 30
15.0	20.0	0 to 40
18.0	24.0	0 to 40
28.0	38.0	0 to 60
58.0	78.0	0 to 100



# Excess Air Device / Separation Tank

The KTM Series pump user manual must be fully read and understood before operating the pump. Failure to do so may result in death, serious injury, or property damage. This page is intended for a basic understanding of the KTM startup operation and is not a substitute for the user manual.

#### PRE-OPERATION CHECK (POWER OFF)

- 1) Prime KTM with effluent or water
- 2) Fully open Suction valve and Discharge valve. Do not run KTM with these valves closed.

#### STARTING THE KTM

#### 1) Discharge side adjustments:


Slowly tighten the Discharge valve until the discharge pressure falls within the desired range of 0.3MPa to 0.4Mpa (approximately 3 bar to 4 bar) with reference to the Pressure gauge. In the case where the Discharge valve (or KTM) is located far from the flotation tank, bubbles will tend to grow larger. In order to maintain microbubble size, an additional control valve should be installed on the flotation tank side to control the discharge pressure.

#### 2) Suction side adjustments:

Check to see if the Compound gauge indicates a negative suction pressure between the range of -0.02MPa to -0.03MPa (approximately -0.2 bar to -0.3 bar). If the pressure is higher than this range, slightly tighten the Suction valve to bring the pressure into the range stated above.

#### 3) Air injection adjustments:

Open the knob of Air-Parameter (Air flow meter) and adjust to an air flow rate that is 8% of the water flow rate.




In case of mini bubbles occur and effect to flotation process, please consider installing Excess Air Device / Separation Tank as shown in next page.






# Reference P&ID for DAF System



## Recommended Separation Tank Capacity



Model	A (mm)	B (mm)	Capacity (Liter)
KTM20N(F)(D)	100	260	2
KTM25N(F)(D)	120	350	4
KTM32N(F)(D)	260	400	20
KTM40N(F)(D)	260	400	20
KTM50S(F)1,S(F)2,S(F)3	300	850	60
KTM65S(F)2	450	900	140
KTM80S(F)	450	900	140